BANGALORE DIVISION. [ADVERTISEMENT.

Notification, dated 15th January 1896.

[redacted] is hereby given that sealed tenders will be received at the office of the Executive Engineer, [redacted]alore Division, up to 1st February 1896, for constructing Record Rooms to the District Office, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 189

2. The plans, detailed estimate and conditions, may be seen at the Executive Engineer's office at Bangalore between the hours of 11 to 5 P. M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Record Rooms to the District Office, Bangalore," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

MEMO FOR CONSTRUCTING RECORD ROOMS TO THE DISTRICT OFFICE, BANGALORE.

Details of Work.	*Per.*	*Quantity.*
Earthwork excavation	C.yds.	103
Do filling basement	Do	138
Burnt stone in chunam (foundation and basement)	C.ft.	3,761
Brick in chunam, superstructure..	Do	6,108
Plastering with chunam	Sq.	110·62
Whitewashing	Do	51·88
Colour washing	Do	58·74
Pointing with chunam	Do	7·74
Terrace roofing	Do	17·11
Flooring with Cuddappa stones	Do	15·47
Stone slabs	S.ft.	11·55
Cornice ($1\frac{1}{3} \times 1\frac{1}{3}$)	R.ft.	238
Do ($\frac{3}{4} \times \frac{3}{4}$)	Do	80
String course	Do	556
Fillet moulding	Do	396
Finials	E.	12
Archwork brick in chunam	C.ft.	243
Teakwood work	Do	601
Door $4' \times 8\frac{3}{4}$ including frames	S.ft.	35
Windows double with glass shutters inside and perforated iron shutters outside, and with iron bars $3\frac{1}{2}' \times 14\frac{1}{4}' = 49\frac{7}{8}$ Sq.ft.	Do	1,227
Teakwood work for record racks	L. S.	..
For levelling ground, drainage pipes, &c.	Do	..
Ventilators	Do	..

Y. SRINIVASA RAO,
Executive Engineer, Bangalore Division.

IN THE COURT OF THE MUNSIFF, SHIMOGA.

Original Suit No. 772 of 1895-96.

Plaintiff.		*Defendants.*
Gows Sheriff Saheb, resident of Shimoga.	*vs*	1. Syed Mohdin Saheb of Shikarpur. 2. Muse Khah of Shimoga.

NOTICE.

Whereas that Syed Mohdin Saheb, son of Syed Jafar, Inspector of Police, Shikarpur Taluk, having obtained a house attached to the Jumma Maszid at Shimoga, on a rental of Rs. 60 per annum